

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Special repairs and painting the fire damaged area at office room and corridor in the Department of English

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	290.00		sqm	
2. 13.4 3.1	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface - water thinnable cement primer	290.00		sqm	
3. 13.60. 1	Wall painting with acrylic emulsion paint of approved brand and manufacturer to give an even shade - Two or more coats on new work	140.00		sqm	
4. 13.47. 1	Finishing walls with premium acrylic smooth exterior paint with silicone additives of required shade - New work (two or more coats applied @1.43 ltr / 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg / 10sqm)	110.00		sqm	
5. 6.4.1	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in superstructure above plinth level upto floor five level in all shapes and sizes in - cement mortar 1:4 (1 cement : 4 coarse sand)	1.00		cum	
6. 13.1.2	12mm cement plaster of mix -1:6 (1 cement: 6 fine sand)	1.50		sqm	
7. 14.54. 1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	14.00		sqm	

8. 9.84	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564 , embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm) , with double speed adjustment with necessary accessories and screws etc.complete	2.00		each	
9. 11.26. 1	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab,including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand) - 25 mm thick	2.00		sqm	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer