

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and fixing PVC flooring, false ceiling and special repairs to the newly established seminar hall at department of Biochemistry and Molecular Biology

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.1 3.1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50m lead - Of area 3 sq. metre and below.	4.00		Each	
2. 9.21. 2	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. - 30mm thick including ISI marked stainless steel butt hinges with necessary screws.	8.00		Sqm	
3. 9.23	Extra for providing lipping with teak wood battens 25mm minimum depth on all edges of r area shutters (over all area of door shutter to be measured) over item no.9.20 and 9.21	8.00		Sqm	
4. 12.7 2	Providing and fixing false ceiling works using superiorfire rated gypsum board of 12.5mm tk mounted on GI frame work with ceiling section of size 80x26x0.55x3660 mm spacing at 600mm c/c suspended from ceiling using hanger rods at 1200mm c/c with screw to level and line and applying one coat of primer , two coats of putty followed by and reflective paint in front of the stage area to the required shape and size , including scaffolding etc.complete as directed by the engineer -in-charge upto 6.5m height	100.00		Sqm	
5. 11.6 3.3	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller	105.00		Sqm	

	weighing about 5 kg. All complete - 2 mm thick sheet				
6. 9.84	Providing and fixing IS:3564 make aluminium extruded section body tubular type universal hydraulic door closer with double speed adjustment with necessary accessories and screws B60etc.complete	4.00		Each	
7. 9.10 0.1	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade as per 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :-125mm	8.00		Each	
8. 9.97. 4	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete : -150x10mm	8.00		Each	
9. 9.96. 1	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc.complete:- 300x16mm	4.00		Each	
10. 9.10 1.2	Providing and fixing aluminium hanging floordoor stopper ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc.complete -Twin rubber stopper	6.00		Each	
11. 13.5 0.1	Applying priming coat - with ready pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	19.00		Sqm	
12. 13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade -Two or more coats on new work.	19.00		Sqm	
13. 14.5 4.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	60.00		Sqm	
14. 13.6 0.1C	Wall painting with plastic emulsion paint - Commercial of approved brand	110.00		Sqm	

	and manufacture to give an even shade - two or more coats on old work				
15. MR	Supplying and fixing fleeted screens at Department of Biochemistry and Molecular Biology using the approved quality screen cloth width not less than 48” with necessary curtain rod rainbow, plastic screen cloth used should be not less than Rs.140 for screen cloth. The rate including all labours and materials etc., complete as per the direction of the Engineer-in-charge.				
	a) Handloom material	36.00		Rmt	
	b) Handloom lining	36.00		Rmt	
	c) Stretching charge	17.00		Part	
	d) Curtain rod rainbow / Marvel	10.00		Rmt	
	e) Rod fixing charge	4.00		Each	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer