

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the existing soil wastepipe to UPVC 160 mm dia pipe from man hole to the septic tank at Subramaniya Bharathiyar hostel

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 31.161. 1J	Providing, laying and jointing UPVC pipes(Finolex / jain / Supreme / Truebore / Nandi) (0.6 Mpa)conforming to IS specification 4985 and ISI marked including transportation to the site , lowering to the trenches, laying to proper grade and alignment, testing of joints with required testing equipment, including cost of solvent cement, excluding UPVC specials such as bends, tees, threaded pieces, couplers, reducer, endcaps etc.,complete all as per IS and CPWD specification. - 160mm dia.	60.00		metre	
2 2.10.1.2	Excavating trenches of required width pipes,cables, etc including excavation for sockets and dressing of sides, ramming of bottoms,depth upto 1.5 m including getting out the excavated soil and then returning the soil as required in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering , etc.and disposing of surplus excavated soil as directed ,within a lead of 50m - All kinds of soil -Pipes,cables etc, exceeding 80mm dia but not exceeding 300 mm dia..	60.00		for metre length of pipe	
3 32.50.1 A	Raising of intercepting chamber by dismantling the old R.C.C. slab, removing the I.C. cover and frame from the chamber and raising the chamber height with brickwork in cement mortar 1:4 (one cement and four sand), refixing the frame in position by laying reinforced cement concrete 1:1.5:3(One cement one and half sand and three HBGmetal) including curing but	5.00		no	

	excluding the cost of reinforcement, finishing the top,inside and outside plastering with 20mmthick in cement mortar 1:3(one cement three sand), the rate includes all materials, providing barricading, caution board, watch and ward etc.,complete till the completion of work with minimum hindrance to the traffic.- 30cm height.				
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer