

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Special repairs to JN auditorium

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.57	Dismantling aluminium / gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer-in charge	80		sqm	
2. 12.53	Providing and fixing 15mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture spintone / cosmos /Hexa or equivalent of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre , and cross 'T' of size 24 x28 mm made out of 0.33 mm (minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form a grid of 1200 x600 mm and secondary cross 'T' of length 600 mm and size 24x28 mm made of 0.33 mm thick (minimum) sheet to be inter locked at middle of the 1200x600mm panel to form grid of size 600x600 mm, resting on periphery walls / partitions on a perimetre wall angle pre-coated steel of size 24x24x3000 mm made of 0.4mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230mm interval and laying 15mm thick densified edges calcium silicate ceiling tiles of approved texture (Spintone /Cosmos/hexa) in the grid, including , cutting / making opening for services like diffusers , grills, light	80		sqm	

	<p>fittings, fixtures , smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I.slotted cleats of size 25x35x1.6mm fixed to ceiling with 12.5mm dia and 50mm long dash fasteners, 4mm G.I.adjustable rods with galvanised steel level clips of size 85x30x0.8mm, spaced at 1200mm centre to centre along main 'T' , bottom exposed with 24mm of all T-sections shall be pre -painted with polyster baked paint, for all heights, as per specifications, drawings - Note:- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/opening (cut out) having area less than 0.30 sqm. The calcium silicate ceiling tile shall have NRC , value of 0.50(minimum), light reflection > 85% ,non - combustible as per B.S.476 Part IV, 100% humidity resistance and also having thermal conductivity < 0.043 w/m 0 KC</p>				
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer