

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of the work: Providing temporary fencing with barbed wire in open portions of compound wall at University campus

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 16.18.1	Fencing with angle iron post placed at required distance embedded in cement concrete blocks , every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal two diagonals interwoven with horizontal wires, of barbed wire 9.38 kg per 100 metre (minimum) between the two posts fitted and fixed with G.I.staples , turn buckles etc complete (cost of posts , struts, earth work and concrete work to be paid for separately):- Payment to be made per metre cost of total length of barbed wire used - with G.I.barbed wire	876.00		metre	
2. 16.19	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction of 10 cm length and drilling holes upto 10mm dia etc.complete	382.00		kg	
3. 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavation) / manual means over areas (exceeding 30 cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth, lead upto 50m and lift upto 1.5m - all kinds of soil	2.15		cum	
4. 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	2.15		cum	
5. 13.50.3	Applying priming coat - with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron / steel works	20		sqm	

6. 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	14		sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**