PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Creating door opening to the room between HVAC unit above the video production studio department of electronic media and Research center

S.	Description	Qty.	Rate	Unit	Amount
No.			Rs.P.		Rs.P.
1 14.4.1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete to match existing surface i/c disposal of mulba / rubbish to the nearest dumping ground - for door/window/clerestory window	0.50		Cum	
2 9.1.2V	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia& length (hold fast lugs or dash fastener shall be paid for separately) -Vengai wood	0.04		Cum	
3 9.20.2	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part 1) decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters – 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.10		Sqm	
4 11.41.2 A	Providing and laying fully vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson /Asian) in all colours and	32.00		Sqm	

	shades , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) , including grouting the joints with white cement and matching pigments etc., complete - size of tile 600 x600 mm			
5 6.3.1	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level upto floor five level in cement mortar 1:6 (1 cement: 6 coarse sand) - with F.P.S (non - modular) bricks	4.00	Cum	
6 9.53	Providing 40 X 5 mm flat iron hold fast 40 cm long including fixing to frame with 10mm diameter bots, nuts and wooden plugs andembeddings in cement concrete block 30 x10x 15 cm 1:3:6 mix (1 cement : 3 coarse sand: 6 graded stone aggregate 20mm nominalsize	6.00	Each	
7 13.2.1	15mm cement plaster on the rough side of single or half brick wall of mix - 1:4 (1cement : 4 fine sand)	104.00	Sqm	
8 13.85.3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content - with water thinnable cement primer on wall surface having VOC content less than 50 grams / litre	104.00	Sqm	
9 13.60.1	Wall painting with acrylic emulsion paint of approved brand and manufacturer to give an even shade - Two or more coats on new work	104.00	Sqm	
10 13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and	5.00	Sqm	

	manufacture			
9.83	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS:3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc complete	1.00	Each	
9.100.1	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc, complete - 125 mm	2.00	Each	
13 9.97.1	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868), transparent or dyed to required colour or shade, with necessary screws etc. complete - 300 x10 mm	2.00	Each	
14 9.96.1	Providing and fixing aluminium sliding door bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with nuts and screws etc complete - 300 X 16 mm	1.00	Each	
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.