

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Providing and fixing screen cloth and wall painting at CEs office

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	220.00		sqm	
2 13.43.1	Applying one coat of water thinnable cement of approved brand and manufacturer on wall surface - water thinnable cement primer	220.00		sqm	
3 13.60.1	Wall painting with acrylic emulsion paint of approved brand and manufacturer to give an even shade - Two or more coats on new work	220.00		sqm	
4 14.67.1	Finishing walls with premium acrylic smooth exterior paint with silicon additives of required shade - old work (two or more coats applied @ 1.43 ltr / 10 sqm) over existing cement paint surface	320.00		sqm	
5 MR	Supplying and fixing Fleet screen using approved quality screen cloth with not less than 1200 mm width with necessary curtain rod rainbow with all fittings , screen cloth should be not less than Rs 140.00 for screen cloth . and not less than Rs 75.00 for inner lining material the rate includes of all labour charge for material, transport , and fixing charges etc., complete as per the direction of engineer in charge				

	a) For handloom materials	112.00		mt	
	b) Inner material	112.00		Mt	
	c) Stitching charge `	106.00		Each	
	d) Curtain rod	30.00		Mt	
	e) Rod fixing charge	12.00		Each	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**