

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged floor tiles at first floor corridor near controller office room at Examination building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.2 3.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead – for thickness of tiles 10mm to 25mm	22		sqm	
2. 11.4 1.2A	Providing and laying fully vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622 of approved make (Nitco / Rak / Johnson /Asian) in all colours and shades , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) , including grouting the joints with white cement and matching pigments etc., complete - size of tile 600 x600 mm	22		sqm	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer