

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Enlarging the Ph.d section at Examination Wing

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 21.1.1 .2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS:733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions ,i.e at top, bottom and sides with required EPDM rubber / neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, aluminium snap beading for glazing / paneling , C.P.brass / stainless steel screws , all complete as per architectural drawings (Glazing, paneling and dash fasteners to be paid for separately) - for fixed portion – Powder coated aluminium (minimum thickness of powder coating 50 micron)	50.00		Kg	
2 21.2. 2	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 grade I type II , in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings- Pre - laminated particle board with decorative lamination on both sides	18.00		Sqm	
3 14.4.1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the	9.00		Sqm	

	damages to walls, flooring and jambs complete to match existing surface i/c disposal of mulba / rubbish to the nearest dumping ground - for door/window/clerestory window				
--	---	--	--	--	--

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer