

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Special works at Gents gym building Pondicherry University

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 14.1.1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq.metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead -with cement mortar 1:4 (1 cement : 4finesand)	5.00		Sqm	
2 11.63.3	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5 kg. All complete - 2 mm thick sheet	85.00		sqm	
3 9.135.1 B	Providing and fixing fly proof stainless steel grade 304 wire gauge , to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.50 mm all complete - with Burma teak wood beading 62x 19 mm	30.00		sqm	
4 2.34.1	Supplying chemical emulsion in sealed containers including delivery as specified- Chlorpyriphos / lindane emulsifiable concentrate of 20%	30.00		litre	
5 2.35.2.1	Diluting and injecting chemical emulsion for POST - CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) - along the external wall below concrete or masonry apron using chemical emulsion @ 2.25 litres per linear meter including drilling and plugging holes etc.- with chlorpyriphos lindane E.C.20% with1% concentration.	110.00		metre	

6 2.35.4.1	Diluting and injecting chemical emulsion for POST - CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) - Treatment of existing masonry using chemical emulsion @ one litre per hole at 300mm interval including drilling holes at 45 degree and plugging them with cement mortar 1:2 ( 1 cement : 2 coarse sand) to the full depth of the hole – withc hlorpyriphos / lindane E.C. 20% with 1%concentration	100.00		metre	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**