

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of the work: Providing and fixing of stainless steel mesh to the windows at ladies gym building

<b>Sl No:</b>	<b>Description</b>	<b>Qty</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1. 9.51. 1B	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4mm in both directions with wire of dia 0.63 mm all complete - with Burma teak wood beading 62 X 19 mm [Each window which consisting of horizontal 2.25 mt (2 nos) and vertical 1.60mt (3nos.) ]	38		sqm	
2. 13.5 0.1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	17		sqm	
3. 13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	17		sqm	
4. 14.5 4.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	35		sqm	
	<b>TOTAL</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**