

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Replacement of G.I pipe inlet line to tank on wall face at Sarvapalli Radhkrishnan, Moulana Abulkalam Azad, Valmiki, Kannadasan, Kabirdass hostel and Guest House-II

Sl. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 18.9.15	Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 50mm nominal outer dia pipes	20		metre	
2. 18.9.16	Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 63mm nominal outer dia pipes	153		metre	
3. AR	Providing and fixing ASTM valve of approved quality – 63 mm dia	9		Nos.	
4. AR	Providing and fixing ASTM valve of approved quality – 50 mm dia	2		Nos.	
5. MR	Labour engagement for earth work excavation for jointing the existing pipe line laid at below the ground level and refilling etc complete as directed	4		Nos.	
6. AR	Dismantling G.I pipe by manually including stacking of pipes within 50 m lead- 15mm to 50 mm nominal bore	173		Metre	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer