

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of work: Fabrication and providing galvalume sheet shed at Centre for Nano Science and Technology

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1. MR	Fabrication and providing galvalume sheet shed of size 3(L)x2(W)x2(D) clear by using M.S. angles, flats etc., as per the drawing enclosed. The roofing truss along with purlin used M.S.Square tube and 0.5mm thick galvalume sheet over the truss portion. The base support has to be provided 30cm cement concreted as a pedestal (PCC - 1:5:10 - 15cm and PCC - 1:2:4 – 15Cm). The galvalume shed has to be fabricated with 1m wide door provision by using M.S. angle and 20 Gauge G.I sheet wherever required as per the drawing enclosed. The quoted rate inclusive of all materials cost and labour charges including one coat of cement primer, two coat of enamel paint etc., complete as directed by the Engineer-in-charge. The shed has to be fabricated at the site of work with due verification of materials used as per the drawing etc.,	1.00		Job	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**