

**PONDICHERY UNIVERSITY**

**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of work: Replacing the damaged door shutter and frames at B-9, B-11, F-21, F-28, G-1, G-17, and D-21 quarters building

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1. 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead - of area 3 sqm and below	3		each	
2. 15.13.1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead - of area 3 sqm and below	4		each	
3. 9.1.2P	Providing wood work in frames of doors , windows, clerestory windows and other frames , wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) - Padak wood	0.20		cum	
4. 9.53	Providing 40 X 5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30 x10 x 15 cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	8		each	
5. 9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part 1) non - decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters - 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	12		sqm	
6. 9.23	Extra for providing lipping with teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured)	12		sqm	
7. MR	Replastering and finishing the damaged cutting/ dismantled portion of the around the door frame wall et complete as directed by the Engineer-in-charge	3		No.	

8. 9.97.3	Providing and fixing aluminium tower bolts , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) , transparent or dyed to required colour or shade , with necessary screws etc. complete - 200 x10 mm	7		each	
9. 9.96.2	Providing and fixing aluminium sliding door bolts , ISI marked , anodised ( anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade , with nuts and screws etc complete - 250 X 16 mm	5		each	
10. 9.100.1	Providing and fixing aluminium handles , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade,with necessary screws etc, complete - 125 mm	18		each	
11. 9.97.2	Providing and fixing aluminium tower bolts , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) ,transparent or dyed to required colour or shade , with necessary screws etc. complete - 250 x10 mm	7		each	
12. 9.101.2	Providing and fixing aluminium hanging floor door stopper , ISI marked , anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc complete - Twin rubber stopper	9		each	
13. 13.50.1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	30		sqm	
14. 13.61.1	Painting with synthetic enamel paint of approved brand and manufacutre to give an even shade - Two or more coats on new work	30		sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer(oc)**