

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Demolishing the brick work and wooden partition to create larger space at stack area in Central Library

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.7.4	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar	17.00		cum	
2. 15.39.3	Dismantling wooden boarding in lining of walls and partitions , excluding supporting members but including stacking within 50 metres lead - thickness above 25mm upto 40mm	110.00		Sqm	
3. 15.14.2	Dismantling wood work in frames, trusses, purlins and rafters upto 10 metres span and 5 metres height including stacking the material within 50 metres lead – of sectional area below 40 square centimetres	210.00		metre	
4. 14.75	Repair to plaster of thickness 12mm to 20mm in patches of area 2.5sqm and under including cutting the patch in proper shape , raking out joints and preparing plastering the wall surface with white cement based polymer modified self-curing mortar , including disposal of rubbish , all complete	30.00		sqm	
5. 14.53.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade - One or more coats on old work	280.00		Sqm	
6. 14.59.1	Polishing on wood work with ready made wax polish of approved barnd and manufacture - old work	51.00		sqm	
7. 9.48.2	Providing and fixing M.S.grills of required pattern in frames of windows etc with M.S.flats , square or round bars etc. including priming coat with approved steel primer all complete - Fixed to openings / wooden frames with rawl plugs screws etc	105.00		kg	
8. 13.61.1	Painting with synthetic enamel paint of approved brand and manufacutre to give an even shade - Two or more coats on new work	7.00		sqm	

9. MR	Erecting wooden partition of size 6 mt x 3.20 mt with available material in shown place as directed by engineer in charge. The rate only for labour charges , but excluding the material but including fastener required for work	1.00		Job	
10. 11.46.2	Providing and laying vitrified tiles of size 600 x600 mm (thickness to be specified by manufacturer), with water absorption less than 0.08% and conforming to IS : 15622 , of approved make , in all colours & shade, in skirting ,riser of steps , over 12 mm thick bed of cement mortar 1:3 (1cement :3 coarse sand), including grouting the joint with white cement & matching pigments etc.complete - size of tile 600x600mm	10.00		sqm	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer(oc)