PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Painting the room no.152,153,154,157,163,165,166,173,177,143,146 in Narmadha hostel building

S.	Description	Qty.	Rate	Unit	Amount
No.			Rs.P.		Rs.P.
1. 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scrarches etc.complete	267		Sqm	
2. 13.43.1	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface - water thinnable cement primer	267		sqm	
3. AR	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade – two or more coats on old work	267		Sqm	
4. MR	Replastering and finishing the damaged portion of the alround door frame walls etc complete as directed by the Engineer-in-charge. The rate include coat of all material and labour charges etc	7		No.	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 05 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer(oc)