

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Providing infra structure facilities to the chambers of newly recruited AR's and DR's

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 14.53.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade - One or more coats on old work	610.00		Sqm	
2 MR	Supplying and fixing Fleet screen using approved quality screen cloth with not less than 1200 mm width with necessary curtain rod rainbow with all fittings , screen cloth should be not less than Rs 140.00 for screen cloth . and not less than Rs 75.00 for inner lining material the rate includes of all labour charge for material, transport , and fixing charges etc., complete as per the direction of engineer in charge				
	a) For Screen materials	61.00		Mt	
	b) Inner material	61.00		Mt	
	c) Stitching charge	50.00		Each	
	d) Curtain rod	17.00		Mt	
	e) Rod fixing charge	12.00		Each	
3. 11.63.1	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5 kg. All complete - 1.5 mm thick sheet	40.00		Sqm	

4. 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	36.00		Sqm	
	<b>TOTAL</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer(oc)**