PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Replacing the damaged false ceiling at Pilot plant and providing 3 way lab tap to lab at Department of Food Science Technology Laboratory

S.	Description	Qty.	Rate	Unit	Amount
	Description	QUJ		Cint	
No.			Rs.P.		Rs.P.
1 15.57	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material within 50m lead.	20.00		sqm	
2	Providing and fixing at all height false				
12.45.1	ceiling including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS :277 and consisting of angle cleats of size 25mm wide X 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to ceiling with dash fastener 12.5mm dia X 40mm long with 6mm dia bolts to the angle hangers of 25X25X0.55mm of required length, and other end of anglehanger being fixed with nut and bolts to the G.I. channels 45X15X0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm dia X 230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and	20.00		sqm	

3	perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall / partition with the help of rawl plugs at 450mm cntre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of taper ed and			
5 13.60.1 A	Wall painting with acrylic emulsion paint of approved brand and manufacturer to givean even shade - Two or more coats on newworK	20.00	sqm	
4 MR	Supply of 3 Way brass lab tap sink cork to department (brand namewater man) the rate includes GST 18%(quotation enclosed	10.00	Each	
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer(oc)