

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Proposed anti skid tiles ramp along with S.S. Hand rail at DDE building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.23. 2	Dismantling tile, marble work in floors and roofs laid in cement mortar including stacking material within 50 metres lead - for thickness of tiles above 25 mm and upto 40 mm	4.00		Sqm	
2. 15.2.1	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.00		Cum	
3. 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc.complete	120.00		Sqm	
4. 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	1.00		Cum	
5. 4.1.4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size)	1.00		Cum	
6. 6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in - cement mortar 1:6 (1 cement : 6 coarse sand)	1.50		Cum	
7. 13.3.2	20mm cement plaster of mix -1:6 (1 cement : 6 fine sand)	10		Sqm	
8. 14.54. 1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	9.00		Sqm	
9. 13.47.	Finishing walls with premium acrylic smooth exterior paint with silicone additives of	10.00		Sqm	

1	required shade - New work (two or more coats applied @1.43 ltr / 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg / 10sqm				
10. 14.67. 1	Finishing walls with premium acrylic smooth exterior paint with silicon additives of required shade - old work (two or more coats applied @ 1.43 ltr / 10 sqm) over existing cement paint surface	120.00		Sqm	
11. 11.40. 1	Providing and laying rectified ceramic rustic / matt finish floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer - minimum 10mm thickness) of 1st quality conforming to IS:15622 of approved make (Somany / Nitco) in all colours, shades, except white, ivory, grey, fume red brown, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete	8.00		Sqm	
12. 10.28	Providing and fixing stainless steel (grade 304) railing made of hollow tubes, channels, plates etc., including welding ,grinding. Buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete. i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.,)	45.00		Kg	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer(oc)