

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Providing cabin, for camera server and UPS, sun control film and curtains to the windows at Madam Curie girls hostels office

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 21.1.1 .1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS:733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions , i.e at top, bottom and sides with required EPDM rubber / neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, aluminium snap beading for glazing / paneling , C.P.brass / stainless steel screws , all complete as per architectural drawings (Glazing, paneling and dash fasteners to be paid for separately) - for fixed portion - anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC 15)	27		kg	
2. 21.1.2 .1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS:733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions , i.e at top, bottom and sides with required EPDM rubber / neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, aluminium snap beading for glazing / paneling , C.P.brass / stainless steel screws , all complete as per architectural drawings (Glazing, paneling and dash fasteners to be paid for separately) - for shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM	10		kg	

	rubber / neoprene gasket required (fittings shall be paid for separately) - Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15)				
3. 21.2.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 grade I type II , in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings- Pre - laminated particle board with decorative lamination on both sides	4		sqm	
4. 21.3.2	Providing and fixing glazing in aluminium door, window , ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings ( cost of aluminium snap beading shall be paid in basic item) - with float glass panes of 5.50 mm thickness	4		sqm	
5. 9.97.3	Providing and fixing aluminium tower bolts, ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) , transparent or dyed to required colour or shade , with necessary screws etc. complete - 200 x10 mm	2		each	
6. 9.100. 1	Providing and fixing aluminium handles , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade,with necessary screws etc, complete - 125 mm	2		each	
7. 9.101. 2	Providing and fixing aluminium hanging floor door stopper , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc complete - Twin rubber stopper	1		each	
8. AR	Supplying and fixing of sun control film ( black) of approved make.The rate include wastage, cost of adhesive compound, labour for fixing and transportation etc. complete as per the direction of the Engineer-in-charge	19		Sqm	
9. 9.96.2	Providing and fixing aluminium sliding door bolts , ISI marked , anodised ( anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade ,	1		each	

	with nuts and screws etc complete - 250 X 16 mm				
10. MR	Supplying and fixing fleeted screens using the approved quality screen cloth width not less than 48" with necessary curtain rod rainbow, plastic screen cloth used should be not less than Rs.140 for screen cloth. The rate including all labours and materials etc., complete as per the direction of the Engineer-in-charge.				
	a) Handloom material	54		Rmt	
	b) Handloom lining	54		Rmt	
	c) Stretching charge	28		Part	
	d) Curtain rod rainbow / Marvel	19		Rmt	
	e) Rod fixing charge	7		Each	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer(oc)**