

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of Work: Providing vinyl flooring at Vice Chancellor's chamber and VC's Secretariat at Administrative block of Pondicherry University

| Sl. No | Description | Qty | Rate | Unit | Amount |
|---------------|---|------------|-------------|-------------|---------------|
| 1. 16.100 | Acid cleaning for the existing Mosaic floors, glazed tiles work and removing the stains and decays to give a glassy look etc complete (The Acid used shall be 32% concentrated hydrochloric acid after taking on the precautionary measures) | 110.00 | | sqm | |
| 2. MR | Providing and fixing homogenous polyvinyl flooring chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighting about 5 kg. All complete- 6.5 mm thick sheet of approved design as directed by the Engineer-in-charge <u>(LG HAUSYS REXCOURT 6.5 MM THICK)</u> | 110.00 | | sqm | |
| 3. MR | Providing and fixing homogenous polyvinyl flooring chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighting about 5 kg. All complete- 1.5 mm thick sheet of approved design as directed by the Engineer-in-charge <u>(LG HAUSYS PALACE 1.5 MM THICK)</u> | 86.00 | | sqm | |
| | TOTAL | | | | |

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Executive Engineer(oc)