

**PONDICHERY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of the work:

Providing and fixing View cutter and wooden barricades from Gate No: I to Administrative Block for an account of 29<sup>th</sup> Annual Convocation.

<b>S.No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 MR	Hire charges for providing temporary vertical enclosure of size 3.6m on front side of Administrative Block to Examination wing front side by using corrugated GI sheets. The G.I. sheets should be fixed over the horizontal supporter of 65mm dia G.I. pipe at spacing not exceeding 1.5mts. With necessary hooks, bolt, net and washers. The inner face of the vertical enclosure should be neatly covered with design cloth as directed by the Engineer-in-charge.	680		Sqm	
2 MR	Hire charges for providing 1.5m height barricading arrangements with Casuarina poles of 75mm dia at 1.5m interval, braced with 3 rows or Casuarina poles of 60mm dia tied with necessary rops/coir. The rate includes of transportation charges for materials digging holes to depth of 45cm in earth/concreted surface etc., for fixing the vertical poles, refilling the holes with available materials including dismantling the barricading arrangements and leveling site after completion of purpose as directed by the	1850		Rmt	

	Engineer-in-charge.				
3 MR	Hire charges for fixing of wooden platform of size 7.32x0.60m made of steel support of 50mm dia at 1.5m interval support along with adjustable jockey. The inner and outer face of the wooden platform should be neatly covered with white cloth etc., complete and removing all the materials after completion of Convocation function as directed by the Engineer-in-charge.	1		Job	

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 5 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate should be inclusive of GST & all taxes etc.

**Contractor**

**Head(C&E)**