PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacement of tube well in lieu of the existing defunct tube well located at quarters pump house near over head tank in Pondicherry University campus

S.	Description	Qty.	Rate	Unit	Amount
No.			Rs.P.		Rs.P.
1.	Conveyance charges for Calyx rig drilling and other accessories	1 Job		Job	
2.	Drilling of 8" dia borewell reaming pipe erection packing of pebbles etc.	140		Feet	•
3.	Labour charges for construction of mud pit By using JCB	1		Job	
4.	Supply of mud Bag	15		Bag	
5.	Conveyance charges for mud bag	1 trip		Per trip	
6.	200 mm dia (8") PVC CM casing pipe (Finolex/Jain)	27		Mtr	
7.	200 mm dia (8") PVC CM slotting pipe (Finolex/Jain)	15		Mtr	
8.	200 mm dia (8") dummy	2		No.	
9.	Conveyance charges for pipe	1 trip		Per Trip	
10.	Supply of pebbles	1.5		Unit	
11.	conveyance charges for pebbles by using TATA Ace	1 trip		Per Trip	
12.	Supply of water tanker	3		Tank	
13.	Hire charges for Developing the borewell by using compressor	3		Hour	
14.	Conveyance charges for Tractor compressor	1		Job	
15	Labour charges for Compressor operator	2		No.	
	TOTAL				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of all taxes etc.,

Head(C&E)