

PONDICHERRY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

Name of the work: Construction of selfie point at various location (3 nos.) at Pondicherry
University
campus

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 2.8.1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as per direction of Engineer-in-charge , within a lead of 50m - all kinds of soil	8.00		Cum	
2. 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded stone aggregate 40mm nominal size)	4.00		Cum	
3. 6.4.2	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 3.5 in superstructure above plinth level upto floor five level in all shapes and sizes in - cement mortar 1:6 (1 cement : 6 fine aggregate)	24.00		Cum	
4. 13.1.2	12mm cement plaster of mix -1:6 (1 cement : 6 fine aggregate) sqm 328.10	82.00		Sqm	
5. 7.38.1. 1	Stone tile work for wall lining upto 10m height with special adhesive over 12 mm thick bed of cement mortar 1:3 (1cement : 3 fine aggregate), including pointing in white cement with an admixture of pigment to match the stone shade - 8mm thick (mirror polished and machine cut edge) - granite stone of any colour and shade	87.00		Sqm	
6. MR	Providing and fixing selfie point board over the brick wall of length 10 feet and by using superior quality ACP gold sheet with the height of 3 feet with the write up of “I Love Pondicherry University” (I♥ & PU Logo) and face of wall provided ACP letters (Pondicherry University) at 2 feet height in trilingual letters in Tamil, English & Hindi. The background of letter finished with WPC board with 12 mm thick etc. complete as directed by the	1.00		each	

	Engineer-in charge as per the drawing enclosed at 3 various locations in the University campus. The rate including labours and material fixing & freight charges etc., complete.				
	Total				

I hereby abode the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Head(C&E)