

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and fixing sign/name board at newly constructed International convention Centre in the University campus

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1.	Fabrication of embossed sign/name board of size 50 × 8 ft, with 3-inch projection of laser cut 3D acrylic letters (2 mm thick), mounted on a 3 mm thick ACP backdrop. The structure shall be supported al-round with required welded MS angle frame of size 70 × 75 × 6 mm with required vertical stiffener not less than 4 nos. & required horizontal stiffeners not less than 2 nos. The signage shall be illuminated using high-brightness Samsung LED (5-year Warranty for LED). The rate includes materials, fabrication and fixing the board over the wall to a height of 60 feet from the ground level by mechanical means/using manpower etc. complete as per the direction of the Engineer-in-charge. (To be executed as per the drawing enclosed)	1.00		Job	
2.	Fabrication of embossed sign/name board of size 24 × 2.5 ft, with 3-inch projection of laser cut 3D acrylic letters (5 mm thick), mounted on a 3 mm thick ACP backdrop. The structure shall be supported al-round with required welded MS frame of size 25 × 25 mm with required vertical stiffener not less than 2 nos. The rate includes materials, fabrication and fixing the board over the wall to a height of 20 feet from the ground level by mechanical means/using manpower etc.. complete as per the direction of the Engineer-in-charge. (To be executed as per the drawing enclosed)	1.00		Job	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

-sd-

Contractor

Head(C&E)