

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Providing and fixing entrance arch with name board for the International convention Centre building

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil dresses - all kinds of soil	4.00		Cum	
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	1.00		Cum	
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	3.00		Cum	
4.	Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 fine aggregate), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels - Granite stone slab of colour black, cherry/ ruby red - area of slab up to 0.50 sqm	5.00		Sqm	
5.	Providing edge moulding to 18mm thick marble stone counters ,vanities etc., including machine	10.00		Metre	

	polishing to edge to give high gloss finish etc. complete - Granite work				
6.	Supplying of 50mm dia G.I pipe (class B) - Jindal of approved quality etc. The rate include cost of material and transport etc.	144.00		Metre	
7.	Supplying of 1 ½ x3/4'' (2mm thick) M.S square tube of approved quality. the rate include cost of material & transport etc	303.00		Kg	
8.	Supplying of 1.50 mm thick M.S plate of size (9'' x 9'') of approved quality. The rate include cost of material & transport etc.	24.00		Nos	
9.	Supplying of G.I sheet 1.20mm thick of approved quality etc, the rate include cost of material, transport and wastage etc.,.	9.00		Sqm	
10.	Supplying of M.S bolt & nut 5/8 x 50mm of approved quality. The rate include cost of material & transport etc.	48.00		Nos	
11.	Synthetic enamel paint on two coats for the truss pipe of vertical and horizontal including primer coat etc. complete as directed by the engineer in charge (As per the drawing enclosed )	1.00		Job	
12.	Fabrication and making truss (horizontal, vertical using welding, cutting machine etc, fixing / installation the truss by using hiring the crane vehicle etc as per the given drawing enclosed the rate include cost of welding rod, hire charge the welding machine , cutting machine, crane charges etc. Complete as directed by the engineering in charge. (As per the drawing enclosed )	1.00		Job	
13.	Providing and fixing the vinyl stickers for size of 40*2 feet and logo 3 feet (round) the entrance arch at International convention centre in the PU campus the rate include all material, labour charges and transport etc, directed by the engineer in charge. (As per the drawing enclosed )	1.00		Job	
	<b>Total</b>				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

**Contractor**

**-Sd-  
Head(C&E)**