

PONDICHERRY UNIVERSITY

ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and laying interlocking paver block in the area of the demolished garden in front of the 100 feet national flag mast at the International Convention Centre building

S.NO	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
1 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00		cum	
2 4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	2.00		cum	
3 16.68.2	Providing and laying 63 mm mm thick factory made rubber moulded hydraulic pressed paver block made by block making machine with strong vibratory compaction and of approved size and design / shape laid in required colour and pattern over and including 50mm thick compacted bed of course sand, filling the joints with fine aggregate etc. all complete	230.00		sqm	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

-sd-
Head(C&E)