

**PONDICHERRY UNIVERSITY**

**ENGINEERING WING**

**SCHEDULE OF WORK**

**Name of the work:** Construction of platform for the 100 feet high National flag mast at International Convention Centre building.

S.NO	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
1 2.8.1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil dresses - all kinds of soil	9.00		Cum	
2 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	7.00		Cum	
3 6.1.2	Brick work with common burnt clay F.P.S. (non modular ) bricks of class designation 3.5 in foundation and plinth in - cement mortar 1:6 (1 cement : 6 fine aggregate) cum	9.00		Cum	
4 2.27B	Supplying and filling with red earth (excluding rock) including cost and conveyance to the work site and stacking to the departmental gauge , spreading in layers not exceeding 20cm in depth , watering and consolidation using 0.5 tonne roller , or wooden or steel rammers etc. complete for making play fields , running tracks and court yards	17.00		Cum	
5 13.3.1	20mm cement plaster of mix -1:4 (1 cement : 4 fine aggregate)	65.00		Sqm	
6 13.46.1	Finishing walls with acrylic smooth exterior paint of required shade - New work (two or more coat applied @ 1.67	15.00		Sqm	

	ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre / 10 sqm				
7 MR	Labour charge for shifting the granite slab from vinyagar temple to ICC, laying the granite slab over the platform excluding the cost of all material etc., complete as directed by the engineer in charge.	42.00		Sqm	
8 AR	Laying the granite slab over the stage by using the cement mortar bed 1:4. The rate includes cost of material and labour charge excluding granite slab etc, complete as per the direction of engineer in charge.	3.00		Cum	
9 8.3.2	Providing edge moulding to 18mm thick marble stone counters ,vanities etc., including machine polishing to edge to give high gloss finish etc. complete - Granite work	40.00		Rmt	
10 AR	Providing and fixing 2.½” dia stainless steel decorative show piece (7308) of approved quality etc. the rate includes cost of material, labour charge for fixing and transport etc, complete as per the direction of engineer in charge.	16.00		Nos	
11 AR	Supplying of stainless steel chain (7315) of approved quality. the rate includes cost of material, labour charge for fixing etc, complete as per the direction of engineer in charge.	13.00		Kg	
	<b>Total</b>				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

**Contractor**

-sd-  
**Head(C&E)**